BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
Schedule - B

NAME OF THE WORK: Filling of potholes in Ward No 15 Kammagondannahalli, Filling of potholes in Ward No 16 Mallasandra , Shettyhalli Sub Division and Filling of potholes in ward 17, Chikkasandra, Filling of potholes in ward 18, Bagalagunte, Filling of potholes in ward 19, T Dasarahalli. Dasarahalli Sub Division in Dasarahalli Zone.

Tender Number: BBMP/2024-25/RD/WORK_INDENT3826

Sl. No	Description of work	Unit	Qty	Sanctioned Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications.	Cum	1069.96	2897.94	Rupees Two Thousand Eight Hundred Ninety Seven and Ninety Three Paise Only
2	Filling Pot Hole and patch repairs with Bituminous Concrete, 40mm (using VG-30 Grade Bitumen) Removal of all failed material, trimming of Completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 503, back filling the pot holes with hot bituminous material as per clause 504 using HMP 40/60 TPH Capacity compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2	Sqm	7133.19	482.42	Rupees Four Hundred Eighty Two and Forty Two Paise Only

3 C.P.H

Signature of the Contractor

K.M.E

Executive Engineer,
Dasarahalli Division,